

1 FIRST START-UP

The purpose of First Start-Up is:

- ▶ Ensure the units have been installed correctly;
- ▶ Ensure the units are able to be operated and maintained safely;
- ▶ Correctly set up and configure the units.

1.1 PRELIMINARY CHECKS

1.1.1 Abnormal or hazardous installation situations



Should any abnormal or hazardous installation situations be found, the TAC shall not perform First start-up and the appliance shall not be commissioned.

These situations may be:

- ▶ appliance installed within premises (excluding GAHP A Indoor, GAHP GS/WS in indoor version and AY00-120);
- ▶ appliance installed within premises without safety valve drain ducting (only for GAHP A Indoor and GAHP GS/WS indoor versions);
- ▶ appliance installations other than type C (only for GAHP A Indoor);
- ▶ failed compliance with minimum clearances;
- ▶ insufficient distance from combustibile or flammable materials;
- ▶ conditions that do not warrant access and maintenance in safety;
- ▶ appliance switched on/off with the main switch, instead of the control device provided (DDC, CCP/CCI or external request);
- ▶ appliance defects or faults caused during transport or installation;
- ▶ gas smell;
- ▶ non-compliant mains gas pressure;
- ▶ non-compliant flue gas exhaust;
- ▶ lack of air ducts exhausted by the fan (only for GAHP A Indoor);
- ▶ all situations that may involve operation abnormalities or are potentially hazardous.